



# ZWICKY TRANSIENT FACILITY

---

## **Commissioning Plan**

Richard Dekany

20 May 2016

University of Maryland

# Outline

- ZTF Technical Commissioning Activities
  - Pre-commissioning Activities
    - HPWREN
  - PTF Decommissioning Activities
  - Metrology Activities
    - Telescope alignment
    - Dome and telescope drive optimization
    - Focal Plane Array alignment
  - “First Light” Activities
    - Transmission validation
    - DIQ validation
  - Reference Fields and the Onset of Transient Science
  - Ongoing Maintenance Activities

# ZTF PRE-COMMISSIONING ACTIVITIES

---

# HPWREN

- HPWREN (High-Performance Wireless Research and Education Network) administered by UCSD/San Diego Supercomputing Center
- HPWREN dates from 2000, and Palomar has been an HPWREN partner since inception.
- Currently (2011) we are an HPWREN Tier-1 Partner, and have made an open-ended institutional commitment to remain so
- HPWREN supports ALL internet connectivity to/from Palomar (data transfer, telepresence & remote observing, personal use)




<http://hpwren.ucsd.edu/>



# ZTF Pre-Commissioning Activities

- HPWREN


- ZTF requires  $> 80$  Mbit/sec average downlink from Palomar to keep up with the nominal  $30 + 15$  sec imaging cadence



# DESY shutter installation

Shutter mock-up test on P48

- In order to:
  - Minimize P48 downtime
  - Gain long time baseline experience with operations
  - Reduce ZTF risk
- We propose to:
  - Install the DESY/Bonn exposure shutter in Fall 2016
  - If delivery slips into Winter 2016, shutter installation could slip until Spring (due to P200 aluminizing, cold working conditions) and we'll miss a season's experience



# New P48 Telescope Control Software

- Legacy robotic control software for P48 provided by Vertex RSI
  - Based on defense antenna technology
  - Comprehensive source code unavailable
  - Missing certain common astronomical TCS functions
- New TCS under development by Palomar Observatory
- Initial rollout tests scheduled for Summer 2016
  - Goal is to prove new TCS well ahead of iPTF decommissioning



# IPTF DECOMMISSIONING ACTIVITIES

---



# iPTF Decommissioning Activities

- The exact date of the last iPTF observing night remains unknown
  - Working with Palomar Chief Engineer, Jeff Zolkower, the project is developing a telescope conversion schedule
- Our guiding principles are:
  - Perform as many ZTF upgrade non-invasively beforehand to minimize total P48 downtime during ZTF conversion
    - Will still require (latest est.) 6-10 weeks of telescope downtime
  - Decommission iPTF sufficiently early to keep summit activities off the critical path for ZTF “First Light” activities
- Not a guarantee, but project detailed schedule is showing 28 Feb 2017 at the last iPTF observing night

# ZTF METROLOGY ACTIVITIES

---


# ZTF Metrology Activities

- P48 Telescope
  - Initially, a small FoV test camera will be used to realign Schmidt Doublet (after maintenance activities) and Trim Plate
  - Allows confirmation of telescope and dome drive slew by the new TCS
- ZTF Camera
  - Focal Plane alignment critical at +/- 10 micron relative in tip, tilt, and piston of each of the 16 science CCDs w.r.t. best focus surface of the telescope
  - Based on experimental results by Gina Duggan, project has adopted 'on-sky' metrology measurement as the fundamental strategy for aligning the FPA
    - Lab metrology system deemed too costly, too great schedule impact, and ultimately not the right metric, as telescope details are not sufficiently precisely known
    - Alignment depends on camera position on the prime focus hub (controlled by hexapod), & the optical figure details of Schmidt Doublet and Trim Plate


# ZTF Metrology Activities

- Filter Exchanger Install and First Test
  - First opportunity to access the telescope to test filter exchange operation in the telescope environment (following extensive lab testing at Caltech)
- Dry Air Handling System Demonstration
  - We must maintain clean, dry air in the environment of the ZTF cryostat window

# FPA Metrology Test using iPTF



# FPA Metrology Test using iPTF



Total number of stars in entire CCD array: 10477, Average number of stars per CCD section: 13  
Average Focus Value for a single star:  $1.1156 \pm 0.0046$  mm  
Average Focus for CCD section (1/75 of CCD):  $1.1143 \pm 0.0011$  mm

Confirmed consistent with PTF  
lab profilometer metrology

# ZTF FIRST LIGHT ACTIVITIES

---



# ZTF First Light Activities

- First Light images will be the first in-focus images across the array
  - Confirm the delivered image quality (DIQ) budget
  - Evaluate impact of tube and dome seeing following telescope mods
  - Confirm ZTF optical transmission
  - Confirm the observing efficiency budget
  - Commission ZTF guide / focus loop
    - Control tip, tilt, focus of the ZTF cryostat as well as HA, Dec guiding of P48
    - Evaluate figure monitoring of P48 primary with focuser imagery

# ZTF REFERENCE FIELDS AND THE ONSET OF TRANSIENT SCIENCE

---

# ZTF Reference Fields

- Beginning shortly after First Light we will begin archiving individual 3k x 3k quadrant images
- Over time, according to scheduling, weather, individual noise properties, etc., these quadrant images will reach a sufficient SNR to enable transient responses
- The ZTF sky will 'open up' to transient science on quadrant image at a time, until the full footprint has achieved sufficient reference depth

# BACKUP SLIDES

---

# Flow-down of DIQ allocation to optomech spec's

Wavelength QE	u' filter 3250-3550-3850 TBD Est. only	g' filter 3980-4670-5360 TBD	R filter 5930-6580-7230 TBD	i' filter 7195-8220-9245 TBD Est. only
DIQ Goal (1D FWHM, arcsec)	N/A	2.20	2.00	N/A
Error Term Allocation				
Atmospheric Effects (z = 30 deg)	1.30	1.25	1.16	1.11
Free Atmospheric Seeing	1.24	1.18	1.10	1.05
Dome and Mirror Seeing	0.35	0.35	0.35	0.35
Atmospheric Refraction	0.13	0.23	0.07	0.04
Telescope	0.99	0.97	1.02	1.02
M1 Figure	0.40	0.40	0.40	0.40
Tracking Errors*	0.50	0.50	0.50	0.50
Vibration	0.39	0.39	0.39	0.39
Hub Tilt Rel to Optical Axis	0.40	0.40	0.40	0.40
M1 (Optical Axis) Tilt Rel to Cell	0.39	0.39	0.39	0.39
Schmidt Plate Axial Position	0.04	0.04	0.04	0.04
Schmidt Plate Decenter	0.10	0.10	0.10	0.10
Schmidt Plate Tilt	0.10	0.03	0.10	0.10
Schmidt Plate Aspheric Coeff	0.19	0.09	0.19	0.19
Schmidt Plate Index of Refraction	0.17	0.17	0.28	0.28
Schmidt Plate Abbe Number	0.13	0.13	0.21	0.21
Instrument	1.84	1.57	1.14	1.61
Optical Design IQ (full field avg)	1.60	1.29	0.83	1.40
Cryostat Decenter	0.18	0.18	0.16	0.18
Deviation from Best Focus (Hub motion)*	0.31	0.28	0.31	0.31
Cryostat Window Rel to FPA	0.10	0.10	0.03	0.10
Cryostat Window Opt v. Mech Axis	0.19	0.19	0.05	0.19
Cryostat Window Center Thickness	0.12	0.12	0.07	0.12
Cryostat Window Glass Melt Index, n	0.12	0.12	0.08	0.12
Cryostat Window Thermal Variation in n	0.06	0.06	0.06	0.06
Optics Manufacturing Surface Errors	0.23	0.23	0.23	0.23
Mosaic Tilt Rel to Cryostat	0.21	0.21	0.21	0.21
CCD Surface Relative to Plate	0.27	0.27	0.27	0.27
FPA Plate Height Relative to Hub	0.11	0.11	0.11	0.11
Field Flatteners Tilt	0.10	0.10	0.05	0.10
Field Flatteners Decenter	0.10	0.07	0.10	0.10
Field Flatteners Opt v. Mech Axis	0.16	0.12	0.16	0.16
Field Flatteners Power	0.10	0.10	0.10	0.10
Field Flatteners Final Temperature	0.02	0.02	0.02	0.02
CCD Lateral Diffusion	0.63	0.63	0.48	0.42
Margin (Unmodelled / Implimentation Errors)	0.25	0.25	0.56	0.25
RMS Total DIQ	2.47	2.24	2.00	2.22

given  
assumptions--presently unmodeled/unverified  
potential for improvement?  
dewar design constraints

Area-weighted average across focal plane. Only r' and g' drive design.

K Seeing for other zeniths  
45 degrees  
1.24 arcsec

Based on 1.1" FWHM average (30 degees zenith angle) from 2006/07 P18 MASS/DIMM measurement for Palomar  
uncertain  
refraction from Fillipenko 82

uncertain  
PTF Measured 0.92? TBC  
RMS temporal (high frequency) error =  
PTF Measured: 0.27

(TBC feasibility w/ P. Gardner)

based on ZTF spot size .zpl macro

assume telescope refocus

Amplitude (1/2 P-V) error =  
Amplitude (1/2 P-V) tilt over 373 mm at  
Amplitude (1/2 P-V) flatness =  
Amplitude (1/2 P-V) flatness =

uncertain (esp. vs. wavelength)

Allocation


arcsec FWHM

ALLOCATED TOLERANCES	
10 microns	implies at F/2.45 and
17.7 microns	implies *
10 microns	implies *
10000 microns	implies *
1000 microns	implies *
34.9 milliradians	implies *
5%	implies *
0.05 index uncertainty	results in
1.00 Abbe V uncertainty	results in
150 microns (1-D)	results in
10 microns	implies *
290 microns (1-D)	results in
500 microns (1-D)	results in
100/500 microns	results in
0.002 index	results in
30 K radial gradient	results in
10 microns	implies *
0.05 milliradian error	implies *
12 microns	implies *
5 microns	implies *
9.4 milliradian error	results in
310 microns (1-D)	results in
500 microns (1-D)	results in
10% error	results in
10 K uncertainty	results in

0.39	arcsec
0.40	arcsec
0.39	arcsec
0.04	arcsec
0.10	arcsec
0.10	arcsec
0.19	arcsec
0.28	arcsec
0.21	arcsec

0.18	arcsec
0.31	arcsec
0.10	arcsec
0.19	arcsec
0.12	arcsec
0.12	arcsec
0.06	arcsec
0.23	arcsec
0.21	arcsec
0.27	arcsec
0.11	arcsec
0.10	arcsec
0.10	arcsec
0.16	arcsec
0.10	arcsec
0.02	arcsec


assuming all terms are Gaussian



The Caltech engineers  
have been developing

} New spiders, incl. ring  
 } New articulated ZTF camera mount  
 } New access hatches  
 } Bonn shutter interface

Schmidt trim plate mount  
 New baffles  
 Cable routing  
 Tube balance



Vacuum hose  
not present  
when observing